



## 2017 ROAD CONSTRUCTION PROJECTS (ST17-001)

Re: Addendum No. 2 and RFI Responses  
Issued: November 21, 2017

### Addendum #2

**Bid Due Date:** No Changes

### **Plan Changes:**

**1. Plan Sheet 6 of 15 is hereby amended as follows:**

Replace all references of "concrete culvert" to ADS N-12 Soil-Tight. Called dimensions shall remain as before.

**1. Plan Sheet 11 of 15 is hereby amended as follows:**

Replace "6" AWWA C900 PVC Pipe Class 150, DR-18" and "6" 22 1/2° Bend MJ" on the Estimated Sheet Quantities for Sheet 11 with "8" respectively. Interconnection shall be a 6" x 8" hot tap sleeve. See attached revised bid sheet.

Increase Quantity of Fire Hydrant assemblies from "1" to "2". Hydrant assembly at ~Sta 2+51 was not called out. See attached revised bid sheet showing increase from total of 3 to total of 4.

### **Specification Changes:**

**1. Pertinent sections of the Specifications are hereby changed and shall read as follows:**

Replace all references of storm drain (concrete culvert and ADS N-12 Water-Tight) to ADS N-12 Soil-Tight. Called dimensions shall remain as before.

**2. Pertinent sections of Specification 33 11 13 are hereby changed and shall read as follows:**

2.1.D.2:

"Gravity Sewer comply with ASTM D3034, SDR-35."

### RFI Responses

**Q:** Will American Made Material be required for this project?

**A:** American-made material will NOT be required.



11-21-17

00 44 00.13 BASIS OF BID EXHIBIT

2017 ROAD CONSTRUCTION PROJECTS

ITEM	QUANTITY	UNIT	DESCRIPTION & UNIT PRICE (LIST UNIT PRICE IN BOTH WORDS AND NUMBERS)	EXTENDED PRICE	
1	1	LS	MOBILIZATION		
			DOLLARS & CENTS	\$	
			PER LUMP SUM (\$ _____ )		
2	1	LS	BONDS AND INSURANCE		
			DOLLARS & CENTS	\$	
			PER LUMP SUM (\$ _____ )		
3	1	\$\$	CONTINGENCY		
			FIFTY THOUSAND ZERO	DOLLARS & CENTS	\$50,000.00
			PER FORCE ACCOUNT (\$ 50,000.00 _____ )		
4	1	LS	MATERIALS TESTING		
			DOLLARS & CENTS	\$	
			PER LUMP SUM (\$ _____ )		
5	1	LS	TRAFFIC CONTROL		
			DOLLARS & CENTS	\$	
			PER LUMP SUM (\$ _____ )		
6	7	ACRE	CLEARING AND GRUBBING		
			DOLLARS & CENTS	\$	
			PER ACRE (\$ _____ )		

**2017 ROAD CONSTRUCTION PROJECTS**

ITEM	QUANTITY	UNIT	DESCRIPTION & UNIT PRICE (LIST UNIT PRICE IN BOTH WORDS AND NUMBERS)	EXTENDED PRICE
7	750	CY	UNCLASSIFIED EXCAVATION	
			DOLLARS & CENTS	\$
			PER CUBIC YARD (\$ _____ )	
8	560	CY-MI	HAULING OF EXCESS SOIL	
			DOLLARS & CENTS	\$
			PER CUBIC YARD-MILE (\$ _____ )	
9	1	LS	GRADING AND COMPACTION	
			DOLLARS & CENTS	\$
			PER LUMP SUM (\$ _____ )	
10	7880	CY	FLEXIBLE "CALICHE" BASE	
			DOLLARS & CENTS	\$
			PER CUBIC YARD (\$ _____ )	
11	2100	GAL	PRIME COAT (SS-1)	
			DOLLARS & CENTS	\$
			PER GALLON (\$ _____ )	
12	3420	TON	TxDOT TYPE "D" HOT MIX ASPHALT CONCRETE (HMAC)	
			DOLLARS & CENTS	\$
			PER TON (\$ _____ )	

**2017 ROAD CONSTRUCTION PROJECTS**

ITEM	QUANTITY	UNIT	DESCRIPTION & UNIT PRICE (LIST UNIT PRICE IN BOTH WORDS AND NUMBERS)	EXTENDED PRICE
13	9280	LF	CURB & GUTTER/LAYDOWN CURB	
			DOLLARS &	
			CENTS	\$
PER LINEAR FOOT (\$ _____ )				
14	1	EA	REMOVE AND REPLACE EXISTING CULVERT	
			DOLLARS &	
			CENTS	\$
PER EACH (\$ _____ )				
15	180	LF	REMOVE EXISTING CURB & GUTTER	
			DOLLARS &	
			CENTS	\$
PER LINEAR FOOT (\$ _____ )				
16	350	SF	REMOVE EXISTING SIDEWALK	
			DOLLARS &	
			CENTS	\$
PER SQUARE FOOT (\$ _____ )				
17	620	LF	SAW CUTTING HMAC PAVEMENT	
			DOLLARS &	
			CENTS	\$
PER LINEAR FOOT (\$ _____ )				
18	160	LF	18" N-12 SOIL TIGHT INTEGRATED BELL PIPE	
			DOLLARS &	
			CENTS	\$
PER LINEAR FOOT (\$ _____ )				

**2017 ROAD CONSTRUCTION PROJECTS**

ITEM	QUANTITY	UNIT	DESCRIPTION & UNIT PRICE (LIST UNIT PRICE IN BOTH WORDS AND NUMBERS)	EXTENDED PRICE	
19	2	EA	18" CONCRETE DUAL SAFETY END TREATMENT (TXDOT "SET P-PD")		
			DOLLARS & CENTS		\$
			PER EACH (\$ _____)		
20	8	CY	CONCRETE FILL		
			DOLLARS & CENTS		\$
			PER CUBIC YARD (\$ _____)		
21	10	EA	ADJUST MANHOLE/VALVE COVER TO FINISHED GRADE		
			DOLLARS & CENTS		\$
			PER EACH (\$ _____)		
22	4	EA	POTHOLING AND VERIFICATION OF EXISTING PIPE		
			DOLLARS & CENTS		\$
			PER EACH (\$ _____)		
23	72	CY	6" THICK CONCRETE DRIVEWAYS - REINFORCED		
			DOLLARS & CENTS		\$
			PER CUBIC YARD (\$ _____)		

**2017 ROAD CONSTRUCTION PROJECTS**

ITEM	QUANTITY	UNIT	DESCRIPTION & UNIT PRICE (LIST UNIT PRICE IN BOTH WORDS AND NUMBERS)	EXTENDED PRICE
24	8	EA	FIBERGLASS MANHOLE (COMPLETE) (FURNISHED, INSTALLED, COMPLETED IN-PLACE)	
			DOLLARS &	
			CENTS \$	
			PER EACH (\$ _____ )	
25	630	LF	8" PVC SDR 35 SEWER LINE (FURNISHED, INSTALLED, COMPLETED IN-PLACE)	
			DOLLARS &	
			CENTS \$	
			PER LINEAR FOOT (\$ _____ )	
26	1380	LF	10" PVC SDR 35 SEWER LINE (FURNISHED, INSTALLED, COMPLETED IN-PLACE)	
			DOLLARS &	
			CENTS \$	
			PER LINEAR FOOT (\$ _____ )	
27	16	EA	4" SEWER SERVICE CONNECTION (COMPLETE) (FURNISHED, INSTALLED, COMPLETED IN-PLACE)	
			DOLLARS &	
			CENTS \$	
			PER EACH (\$ _____ )	
28	11	EA	6" SEWER SERVICE CONNECTION (COMPLETE) (FURNISHED, INSTALLED, COMPLETED IN-PLACE)	
			DOLLARS &	
			CENTS \$	
			PER EACH (\$ _____ )	

**2017 ROAD CONSTRUCTION PROJECTS**

ITEM	QUANTITY	UNIT	DESCRIPTION & UNIT PRICE (LIST UNIT PRICE IN BOTH WORDS AND NUMBERS)	EXTENDED PRICE
29	680	LF	8" AWWA C900 PVC PIPE CLASS 150, DR-18 (FURNISHED, INSTALLED, COMPLETED IN PLACE)	
			DOLLARS &	
			CENTS	\$
			PER LINEAR FOOT (\$ _____ )	
30	1000	LF	12" AWWA C900 PVC PIPE, DR-18 (FURNISHED, INSTALLED, COMPLETED IN PLACE)	
			DOLLARS &	
			CENTS	\$
			PER LINEAR FOOT (\$ _____ )	
31	1	EA	6" LATERAL PRESSURE INTERCONNECTION (HOT TAP) W/6" GATE VALVE (FURNISHED, INSTALLED, COMPLETED IN PLACE)	
			DOLLARS &	
			CENTS	\$
			PER EACH (\$ _____ )	
32	4	EA	FIRE HYDRANT ASSEMBLY W/6" GATE VALVE (COMPLETE) (FURNISHED, INSTALLED, COMPLETED IN PLACE)	
			DOLLARS &	
			CENTS	\$
			PER EACH (\$ _____ )	
33	1	EA	8" DUCTILE IRON 22.5° BEND - MJ	
			DOLLARS &	
			CENTS	\$
			PER EACH (\$ _____ )	

**2017 ROAD CONSTRUCTION PROJECTS**

ITEM	QUANTITY	UNIT	DESCRIPTION & UNIT PRICE (LIST UNIT PRICE IN BOTH WORDS AND NUMBERS)	EXTENDED PRICE
34	1	EA	12" DUCTILE IRON 22.5° BEND - MJ	
			DOLLARS &	
			CENTS	\$
PER EACH (\$ _____ )				
35	3	EA	12" DUCTILE IRON 45° BEND - MJ	
			DOLLARS &	
			CENTS	\$
PER EACH (\$ _____ )				
36	2	EA	12" X 6" DUCTILE IRON REDUCER - MJ	
			DOLLARS &	
			CENTS	\$
PER EACH (\$ _____ )				
37	2	EA	12" GATE VALVE - MJ	
			DOLLARS &	
			CENTS	\$
PER EACH (\$ _____ )				
38	16	EA	3/4" WATER SERVICE CONNECTION (COMPLETE) (FURNISHED, INSTALLED, COMPLETED IN PLACE)	
			DOLLARS &	
			CENTS	\$
PER EACH (\$ _____ )				

**2017 ROAD CONSTRUCTION PROJECTS**

ITEM	QUANTITY	UNIT	DESCRIPTION & UNIT PRICE (LIST UNIT PRICE IN BOTH WORDS AND NUMBERS)	EXTENDED PRICE
39	11	EA	2" WATER SERVICE CONNECTION (COMPLETE) (FURNISHED, INSTALLED, COMPLETED IN PLACE)	
			DOLLARS &	
			CENTS \$	
			PER EACH (\$ _____ )	

<b>TOTAL BASE BID</b>		DOLLARS &
		CENTS
	(\$ _____ )	